

Cabrillo College

6500 Soquel Drive, Aptos, CA 95003

Bid No. B13-07

PARKING LOT “N” PAVING AND OVERLAY PROJECT

Addendum No. 1


This Addendum No. 1 sets forth modifications to portions of the bid and contract documents for the above-referenced work described as:

PARKING LOT “N” PAVING AND OVERLAY PROJECT

Summary:

After feedback from the contractors and evaluating the project it was decided there needed to be some clarifications for the specifications.

- 1) Soil removed from the N Parking lot can be dumped on the Well Road; Cabrillo’s Soils Storage Yard (Across the street from the N lot). Contractor will coordinate any dumping with Facilities Staff Grounds Supervisor.
No organics with a diameter greater than 3 inches.
- 2) For the construction of the Matt Slab, Contractor shall use high early strength concrete with cement conforming to:
“ASTM C150, Type III High Early Strength Cement” with a minimum of 3 day compressive strength of 2500 psi.
- 3) All berms within the limits of work that are currently painted “red” shall be repainted with red paint after the slurry seal applied to them has properly cured.
- 4) The existing asphalt pathway located at the Northeast corner of the parking lot shall receive a slurry seal over the portion of the pathway extending to the back of the sidewalk at Soquel Drive that is not reconstructed.
- 5) The Contractor shall notify the Engineer and the regional notification center, “Underground Service Alert” at 800-642-2444, and other affected utilities at least 2 working days, but not more than 14 calendar days, prior to performing any excavation or other work close to any underground pipeline, conduit, duct, wire or other structure. If the location of utilities requires the hiring of a private utility locating company, the Contractor will be required to pay for all costs for such locating services. The contractor will be required to work around all existing utilities.



Cabrillo College

6500 Soquel Drive, Aptos, CA 95003

B13-07 Addendum No. 1 continued.

6) Substantial Completion/Liquidated Damages:

Substantial Completion is obtained when:

The N lot is repaved **and** all striping is completed. Substantial Completion **must** be reached by the end of the day on Friday, June 14, 2013.

Liquidated Damages for Substantial Completion will be assessed at \$1,500 per day.

Project Completion:

Contractor to return to site between the dates of Saturday, June 15 to Friday, June 28, 2013 to complete painting the curbs after the slurry seal has cured.

Liquidated Damages will be assessed at \$250 per day if project is not completed by end of day, Friday, June 28, 2013. The \$250 liquidated damages will only be assessed after Substantial Completion is obtained.